PROJECT MANUAL
FOR
MUNICIPAL RECREATION COURTS
FOUR-COURT PICKLEBALL FACILITY
WITH THREE-COURT BID ALTERNATE A-1
DEMONSTRATION PACKAGE 001

OWNER:	Fictional Municipal Owner (demonstration only) No real address
ARCHITECT/ENGINEER:	IFI LABS / SYNTHETIC CAD Fictional demonstration designer No professional registration claimed
BIDS DUE:	October 30, 2026 2:00 PM Central Time Fictional Municipal Owner
ISSUED FOR BID:	October 12, 2026 (synthetic)
PROJECT NO.:	DP-001

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION

END OF DOCUMENT 00 0001

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

DOCUMENT 00 0005
CERTIFICATIONS PAGE

This project manual is a fictional synthetic demonstration package prepared by IFI Labs / Synthetic CAD. It has not been prepared, signed or sealed by a licensed professional engineer or architect. No professional registration is claimed. No seal is applied.

Signature	NONE
Date	NOT APPLICABLE
Printed or typed name	NOT APPLICABLE
License number	NOT APPLICABLE
License renewal date	NOT APPLICABLE
Pages, sheets or divisions covered by a seal	NONE

END OF DOCUMENT 00 0005

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

00 0001 Project Manual Title Page
00 0005 Certifications Page
Table of Contents
List of Drawings
00 0200 Instructions to Bidders (issued as a separate document)
00 0700 General Conditions
00 0800 Supplemental Conditions

DIVISION 01 - GENERAL REQUIREMENTS

01 1100 Summary of Work
01 1250 Contract Modification Procedures
01 1290 Payment Procedures
01 1450 Quality Control
01 1780 Closeout Submittals
01 2200 Unit Prices

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 31 13 Chain Link Fences and Gates

SPECIAL CONDITIONS

Definitions, Scope of Work and Site Provisions
Bid Items and Measurement

ADDENDA

Addendum No. 01 (issued separately, October 20, 2026)

END OF DOCUMENT

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

LIST OF DRAWINGS

The following drawings, issued October 12, 2026 (Revision 0, Issued for Bid, synthetic), are part of the Contract Documents:

Sheet	Title
G001	Cover and General Notes
C101	Site / Fence Plan, Base Bid and Alternate A-1
C102	Bid Schedules
F501	Fence and Footing Details
F502	Gate and Windscreen Details

END OF LIST OF DRAWINGS

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

I. GENERAL CONDITIONS

A. AIA Document A201-2017, General Conditions of the Contract for Construction, is the General Conditions between the Owner and the Contractor and is made a part of these Documents. The standard form is not reproduced in this demonstration package.

II. SUPPLEMENTARY CONDITIONS

A. Refer to Section 00 0800, Supplemental Conditions, for amendments to the General Conditions.

END OF DOCUMENT 00 0700

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 00 0800
SUPPLEMENTAL CONDITIONS

ARTICLE 1 - GENERAL PROVISIONS

SC-1.1 Definitions

SC-1.1.1 Where the General Conditions use the term "Architect", read IFI Labs / Synthetic CAD, the fictional demonstration designer.

SC-1.1.2 The Owner is the Fictional Municipal Owner (demonstration only). The Owner's Representative is designated in the Special Conditions.

SC-1.2 Order of Precedence

SC-1.2.1 Addenda govern over all other Contract Documents. The Special Conditions govern over Division 01 and the Specification Sections. The Specification Sections govern over the Drawings. Written dimensions govern over scaled dimensions.

SC-1.2.2 Where documents of equal rank conflict, the Contractor shall submit a written request for information before the question deadline stated in Document 00 0200.

ARTICLE 3 - CONTRACTOR

SC-3.1 Intent

SC-3.1.1 Add the following paragraph: General Requirements govern the execution of the Work of all Sections of the Specifications.

SC-3.2 Review of Contract Documents and Field Conditions

SC-3.2.1 The Contractor shall report in writing any conflict, error, omission or missing dimension discovered in the Contract Documents and shall not assume the missing information. Where the Contract Documents state that a dimension or requirement is not specified, the Contractor shall request it in writing before the question deadline.

SC-3.4 Labor and Materials; Labor Standards

SC-3.4.1 The Project is funded in part by a fictional federal recreation grant. Davis-Bacon labor standards apply to the Work by contract. The applicable wage decision is Fictional Wage Decision FDB-DP001, Modification 0, dated October 5, 2026, summarized in Attachment A of this Section. It is a demonstration document and is not a real wage determination.

SC-3.4.2 The Contractor shall pay not less than the wage rates and fringe benefits for the classification of work actually performed. The wage decision lists no classification titled fence erector or fence installer.

SC-3.4.3 The Contractor shall state, in the Bid, the classification proposed for each type of labor used for fence installation. Any classification not listed is subject to approval through the contracting agency's conformance process before that work starts.

SC-3.4.4 The Contractor shall submit certified payroll weekly and shall attach it to each Application for Payment. Bidders shall include the full stated wage rate and fringe benefits in labor pricing.

SC-3.6 Taxes

SC-3.6.1 The Owner is exempt from sales and use taxes on materials incorporated into the Work. The Owner will furnish exemption certificates. The exemption does not apply to tools, machinery, equipment or supplies not incorporated into the Work.

ARTICLE 9 - PAYMENTS AND COMPLETION

SC-9.3 Applications for Payment

SC-9.3.1 Applications for Payment are submitted monthly. The Owner will retain five percent (5%) of each progress payment until Substantial Completion.

SC-9.5 Decisions to Withhold Certification

SC-9.5.1 The Owner may withhold payment for any Application that does not include current certified payroll.

ARTICLE 11 - INSURANCE AND BONDS

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SC-11.1 Contractor's Liability Insurance

SC-11.1.1 Add the following: limits of liability shall be not less than the following, or greater where required by law:

Coverage	Limit
Commercial General Liability, each occurrence	$1,000,000
Commercial General Liability, general aggregate	$2,000,000
Products and completed operations aggregate	$2,000,000
Automobile Liability, combined single limit	$1,000,000 each accident
Excess or Umbrella Liability, per occurrence	$1,000,000
Workers' Compensation	Statutory

SC-11.1.2 The insurance shall include the Owner, the Architect and the Architect's consultants as additional insureds.

SC-11.2 Bonds

SC-11.2.1 Performance and payment bonds are not required for this demonstration package.

ATTACHMENT A - FICTIONAL WAGE DECISION FDB-DP001 (SUMMARY)

Hourly rates. Modification 0, dated October 5, 2026. These are fictional demonstration values. Do not use them outside this demonstration package.

Classification	Base rate	Fringe benefits
Laborer, common or general	$24.50	$9.10
Power equipment operator, skid steer	$29.80	$11.25
Cement mason, concrete finisher	$28.40	$10.70

END OF SECTION 00 0800

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 01 1100
SUMMARY OF WORK

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Project description: the Project consists of earthwork, aggregate base, hot mix asphalt court pavement, concrete walk, acrylic court surfacing, nets, chain link perimeter and divider fence, swing gates, windscreen, fence guard, benches, erosion control and surface restoration for a four-court pickleball facility (Base Bid) or a three-court pickleball facility (Alternate A-1).

B. Work by others.

C. Contractor use of site and premises.

D. Work sequence.

E. Owner occupancy.

1.2 WORK BY OTHER TRADES

A. Special Conditions items 2 through 9 and 17 through 21 are performed by the Contractor's other trades. They are shown on Sheet C101 for reference and are not part of Section 32 31 13. The fence installer coordinates post locations, footings and sequence with those trades.

B. The Owner will provide one-time layout of the court pavement limits.

1.3 CONTRACTOR USE OF SITE

A. Access to site: limited to the access route and staging area designated by the Owner's Representative.

B. Construction operations: limited to the fence lines and the staging area.

1.4 WORK SEQUENCE

A. Place and cure the hot mix asphalt court pavement before setting fence posts. Footing holes are cored through the pavement after placement. Do not apply acrylic court surfacing until the asphalt has cured at least 14 calendar days.

1.5 OWNER OCCUPANCY

A. The Owner intends the Project to be complete by May 28, 2027.

B. Schedule the Work to accommodate this requirement.

1.6 ALTERNATES

A. Alternate A-1 (three-court enclosure) is bid in lieu of the Base Bid (four-court enclosure). Quantify each option independently. See Sheet C101.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION 01 1100

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 01 1250
CONTRACT MODIFICATION PROCEDURES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Administrative and procedural requirements for requests for information and for changes in the Work.

1.2 REQUESTS FOR INFORMATION

A. Submit each request for information in writing to the Owner's Representative. Number each request and identify the sheet, detail or paragraph concerned.

B. Responses that change the Contract Documents are issued by Addendum before bids and by supplemental instruction or Change Order after award.

1.3 CHANGE PROCEDURES

A. The Architect may issue supplemental instructions for minor changes not involving an adjustment in Contract Sum or Contract Time.

B. The Architect may issue a proposal request describing a proposed change. The Contractor shall return a priced proposal within five days.

C. The Contractor may propose changes by written request describing the change and its effect on Contract Sum and Contract Time.

D. Unit price changes: where unit prices and quantities are predetermined, the Change Order is executed at the contract unit price. Otherwise the change is executed by Construction Change Directive on AIA Document G714 and later included in a Change Order.

E. Change Order form: AIA Document G701.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION 01 1250

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 01 1290
PAYMENT PROCEDURES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Procedures for preparation and submittal of Applications for Payment.

1.2 APPLICATIONS FOR PAYMENT

A. Use AIA Documents G702 and G703 or an equivalent form approved by the Architect. Each Application shall be consistent with previous Applications.

B. Submit one executed copy electronically to the Architect by the 25th day of each month.

C. Attach certified payroll for each payroll period covered by the Application.

D. Payment is based on measured quantities of completed unit price items as stated in Section 01 2200.

1.3 INITIAL APPLICATION FOR PAYMENT

A. The following precede or accompany the first Application:

1. List of subcontractors.
2. List of principal suppliers and fabricators.
3. Contractor's construction schedule.
4. Certificates of insurance.
5. Statement of the labor classifications proposed for fence installation.

1.4 FINAL PAYMENT APPLICATION

A. The following precede or accompany the final Application:

1. Warranties and maintenance agreements.
2. Final cleaning.
3. Completion of items on the Architect's punch list.
4. Final certified payroll.
5. Final waivers of lien from the Contractor, subcontractors and suppliers.
6. Removal of temporary facilities and surplus materials.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION 01 1290

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 01 1450
QUALITY CONTROL

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Quality assurance and control of installation.

B. Tolerances.

C. References.

D. Inspection and testing.

1.2 QUALITY ASSURANCE

A. Monitor quality control over suppliers, manufacturers, products, services, site conditions and workmanship.

B. Comply with manufacturers' instructions. If they conflict with the Contract Documents, request clarification from the Architect before proceeding.

C. Perform work with persons qualified to produce workmanship of the specified quality.

D. The Contractor shall review the Work and verify conformance with the Contract Documents. Correct nonconforming Work and submit a written corrective plan within seven days of discovery.

1.3 TOLERANCES

A. Do not permit tolerances to accumulate. Adjust products to appropriate dimensions before securing them in place.

1.4 REFERENCES

A. Comply with referenced standards, current on the date of the Contract Documents, except where more rigid requirements are specified or required by code.

B. Mention of a reference standard does not alter the contractual relationship or duties of the parties.

1.5 INSPECTION AND TESTING

A. The Owner will employ and pay for inspection and testing of the Work. Notify the Owner's Representative 48 hours before operations requiring inspection.

B. Inspection or testing does not relieve the Contractor of the obligation to perform the Work as required.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION 01 1450

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 01 1780
CLOSEOUT SUBMITTALS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Final completion and closeout procedures.

B. Final cleaning.

C. Project record documents.

D. Warranties.

1.2 FINAL COMPLETION

A. Submit written certification that the Work has been inspected and is complete in accordance with the Contract Documents.

B. Submit the final Application for Payment with the documents required in Section 01 1290.

1.3 FINAL CLEANING

A. Clean debris from courts, walks and surrounding areas before final inspection.

B. Remove waste, surplus materials, rubbish and construction facilities from the site.

1.4 PROJECT RECORD DOCUMENTS

A. Record actual installed products, including manufacturer and model, and any changes made by Addenda or modifications.

B. Mark field changes of dimension and detail, including the installed length of the south fence used to order the windscreen.

1.5 WARRANTIES

A. Provide duplicate copies of manufacturer and installer warranties. Assemble them with a table of contents in a binder and submit before final payment.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION 01 1780

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 01 2200
UNIT PRICES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Measurement and payment criteria applicable to the Work performed under a unit price payment method.

1.2 AUTHORITY

A. Measurement methods stated in the Special Conditions complement this Section. In a conflict, the Special Conditions govern.

B. The Owner's Representative measures the Work and computes quantities.

1.3 UNIT QUANTITIES

A. Quantities on the bid schedules (Sheet C102) are for bidding and contract purposes only. Measured quantities verified by the Owner's Representative determine payment.

B. Base Bid and Alternate A-1 quantities are determined independently.

1.4 MEASUREMENT OF QUANTITIES

A. Linear measurement: by linear dimension along the item centerline.

B. Measurement by each: by count of completed items.

C. Lump sum: measured as a completed item or unit of the Work.

1.5 PAYMENT

A. Payment includes full compensation for all labor, products, tools, equipment, transportation, services and incidentals; erection or installation; overhead and profit.

B. Final payment for unit price Work is the accepted measured quantity multiplied by the contract unit price.

1.6 NON-PAYMENT FOR REJECTED PRODUCTS

A. Payment will not be made for products wasted, products rejected before or after placement, products placed beyond the lines of the Work, or products remaining on hand after completion.

PART 2 PRODUCTS

NOT USED

PART 3 EXECUTION

NOT USED

END OF SECTION 01 2200

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SECTION 32 31 13
CHAIN LINK FENCES AND GATES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Type A 10'-0" high chain link perimeter fence, Type B 42" high chain link divider fence, swing gates G1, G2 and G3, windscreen on the south Type A fence, concrete footings and accessories shown on Sheets C101, F501 and F502.

B. Court base, pavement, surfacing, playing lines, nets and net posts are other items in the Contract, performed by other trades, and are not part of this Section.

1.2 REFERENCES

A. ASTM A392, Zinc-Coated Steel Chain-Link Fence Fabric. ASTM C94, Ready-Mixed Concrete. ASTM F567, Installation of Chain-Link Fence. ASTM F626, Fence Fittings. ASTM F900, Industrial and Commercial Swing Gates. ASTM F1043, Strength and Protective Coatings on Metal Industrial Chain-Link Fence Framework. ASTM F1083, Pipe, Steel, Hot-Dipped Zinc-Coated (Galvanized) Welded, for Fence Structures.

1.3 ORDER OF PRECEDENCE

A. Addenda govern over this Section. This Section governs over the Drawings. Written dimensions govern over scaled dimensions. Where documents of equal rank conflict, the Contractor shall submit a written request for information before the question deadline stated in Document 00 0200.

1.4 SUBMITTALS

A. Product data for framework, fabric, fittings, gate hardware and windscreen.

B. Manufacturer's standard color samples for windscreen.

C. Certified payroll reports as required by Section 00 0800, paragraph SC-3.4.4.

1.5 MEASUREMENT AND PAYMENT

A. Chain link fence is measured by the linear foot along the fence centerline from corner to corner, excluding gate openings. Gate openings are measured face of gate post to face of gate post. Type A and Type B fence are measured separately.

B. Gates are paid per each by tag (G1, G2, G3), complete with posts, footings, frame, fabric, hardware and adjustment.

C. Windscreen is measured by the linear foot along the south Type A fence between corner posts.

D. Base Bid and Alternate A-1 are quantified independently. Alternate A-1 is bid in lieu of the Base Bid. Unit prices and quantities are entered on the bid schedules (Sheet C102).

1.6 FIELD CONDITIONS

A. Verify all dimensions and layout in the field before setting posts. Report discrepancies to the Owner's Representative in writing and await direction.

B. Locate and protect underground utilities through the state one-call system before excavating.

C. Coordinate post locations in or near court pavement with the pavement contractor before placement.

D. The windscreen is ordered after the south fence is installed and measured in the field.

PART 2 PRODUCTS

2.1 FRAMEWORK

A. Hot-dip galvanized steel pipe conforming to ASTM F1083, framework Group IA, Type A coating per ASTM F1043. Sizes are outside diameters. Minimum weights: 2.875 in OD, 5.79 lb/ft; 2.375 in OD, 3.65 lb/ft; 1.900 in OD, 2.72 lb/ft; 1.660 in OD, 2.27 lb/ft.

B. Type A (10'-0" high): terminal, corner and gate posts 2.875 in OD (gate posts for G3: size confirmed with the opening width); line posts 2.375 in OD; top rail and mid rail 1.660 in OD.

C. Type B (42" high): terminal posts 2.375 in OD; line posts 1.900 in OD; top rail 1.660 in OD. No mid rail or bracing.

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

D. Post caps: pressed steel dome type, galvanized, one per post. Rail ends, brace bands, tension bands and rail sleeves: galvanized, ASTM F626.

2.2 FABRIC

A. ASTM A392, Class 1 zinc coating, 9 gauge core wire, 2 in mesh, knuckled top and bottom selvages. Heights: Type A 120 in; Type B 42 in; gate leaves 84 in with 36 in of fixed fabric above the header rail.

2.3 TENSION WIRE, TIES AND BRACING

A. Bottom tension wire: 7 gauge galvanized coil spring wire.

B. Tie wire: 9 gauge aluminum.

C. Tension bars: 3/16 in x 3/4 in galvanized flat bar, one full-height bar at each terminal, corner and gate post, with tension bands at 12 in maximum spacing.

D. Truss rods: 3/8 in diameter galvanized with turnbuckle.

2.4 CONCRETE

A. ASTM C94 ready-mixed concrete, minimum 3,000 psi compressive strength at 28 days, 4 in maximum slump, air-entrained 5 to 7 percent. Site-mixed bagged concrete of equal strength is acceptable for individual footings.

2.5 GATES

A. Swing gates complying with ASTM F900. Gates swing into the court enclosure.

B. Gate frames: 1.900 in OD galvanized pipe, welded or fitted corners. Header rail: 1.660 in OD between gate posts with fixed fabric above the header to the top of the fence.

C. Fabric to match the adjacent Type A fence.

D. One adjustable 3/8 in diameter truss rod per leaf.

E. Hinges: 180 degree malleable, three per leaf.

F. Latch: industrial fork latch with padlock eye.

G. Hold-back: galvanized gate stop with hold-open keeper, one per leaf.

H. Padlocks by Owner.

I. Gate schedule:

Tag	Type	Clear opening	Height	Leaves	Per option
G1	Pedestrian swing	4'-0"	7'-0"	1	1
G2	Maintenance swing	6'-0"	7'-0"	1	2
G3	Service swing	As indicated on the Drawings	7'-0"	1	1

2.6 WINDSCREEN

A. Knitted polypropylene, 88 percent nominal shade, 9'-0" high, reinforced hems, brass grommets at 12 in on center along the top and bottom hems, UV-resistant nylon cable ties.

B. Color is selected by the Owner from the manufacturer's standard colors. The Owner has not yet selected a color.

PART 3 EXECUTION

3.1 PREPARATION

A. Perform the field verification and utility location required by paragraph 1.6.

B. Lay out fence lines from the dimensions on C101, which are to the centerline of posts. Space line posts equally between terminal, corner and gate posts at 10'-0" on center maximum.

3.2 POST INSTALLATION

A. Set posts plumb in concrete footings sized per Detail 3/F501. Footing diameters and depths are minimums below finish grade. Crown the top of concrete to shed water.

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

B. Brace posts until the concrete has cured.

C. Terminate Type B divider fence at a terminal post at each end, in line with the clear court zone limit.

D. Gate posts and footings not otherwise noted are as for terminal posts, Detail 3/F501.

E. Court pavement extends 3'-0" beyond the fence centerline (C101), so footings fall within the pavement. Set posts after the hot mix asphalt is placed. Core drill every footing hole through the pavement and base; do not use a drill rig that damages the pavement edge. Remove drilling slurry from the surface promptly.

F. Delay setting posts until the asphalt is no longer damaged by the materials and equipment.

3.3 RAILS AND BRACING

A. Install top rail continuous through line posts.

B. Type A: install a mid rail at 5'-0" above grade. Provide a horizontal brace rail and diagonal truss rod at each terminal and gate post, and in each direction at corner posts.

C. Type B: no mid rail or bracing.

3.4 FABRIC

A. Install fabric on the court (inside) face of the posts. Stretch taut. Maintain 2 in maximum clearance between the bottom of fabric and grade.

B. Fasten fabric to line posts at 12 in on center and to rails and tension wire at 24 in on center with tie wire. Fasten fabric to terminal, corner and gate posts with tension bars and bands.

C. Install bottom tension wire at 3 in above grade.

3.5 GATES

A. Install gates plumb and level with 2 in maximum ground clearance.

B. Install hold-backs so each open leaf is held clear of the walkway.

C. Adjust hinges, latch and truss rod so gates operate freely.

3.6 WINDSCREEN

A. After the south Type A fence is installed, field measure the installed length and order the windscreen.

B. Install on the inside (court) face of the south fence, full length between corner posts.

C. Lap or butt panel ends at posts only. Tie to the fence at each grommet.

3.7 LABOR COMPLIANCE

A. Labor compliance requirements are stated in Section 00 0800, paragraph SC-3.4. This Section does not establish wage rates or trade classifications.

3.8 CLEANING

A. Remove excavated spoils, concrete waste and packaging from the site. Repair court pavement damaged by the Work at no cost to the Owner.

END OF SECTION 32 31 13

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

SPECIAL CONDITIONS

DEFINITIONS

Wherever used in the General Conditions or in the other Contract Documents, the following terms have the meanings indicated:

A. Owner - Fictional Municipal Owner (demonstration only).

B. Architect - IFI Labs / Synthetic CAD (fictional demonstration designer).

C. Owner's Representative - the person designated in writing by the Owner.

D. Work on Project - Municipal Recreation Courts, Four-Court Pickleball Facility with Three-Court Bid Alternate A-1 (Project No. DP-001).

E. The Contract Documents consist of: Addenda; Instructions to Bidders; Bid Schedules (Sheet C102); Agreement; Special Conditions; Supplemental Conditions; General Conditions; Drawings; and the Specifications (Division 01 and Section 32 31 13).

SCOPE OF WORK

The quantities on the bid schedules represent the Architect's estimate of the Work. The Project is the construction of four pickleball courts (Base Bid) or three pickleball courts (Alternate A-1). The Work includes earthwork, aggregate base, hot mix asphalt pavement, concrete walk, acrylic court surfacing, nets, chain link fence and gates, windscreen, fence guard, benches, erosion control and surface restoration. The Owner may add or delete Work at the contract unit prices.

WASTE SITES AND SALVAGE

Dispose of surplus excavated material, broken concrete and similar waste legally, outside the limits of the site, at a location chosen by the Contractor and at the Contractor's expense.

UTILITIES

The Contractor is responsible for locating utilities through the state one-call system and with the utility owners before excavating, and for coordinating with them. The Contractor bears all costs for locating, protecting, repairing or replacing utilities damaged by the Work. Utilities remain in service unless the utility owner authorizes otherwise. Where a utility is exposed, support it and backfill so as not to cause damage or settlement. Do not use limestone screenings as backfill. If the Work causes a permanent relocation, the Owner will bear the cost of the relocation.

EQUIPMENT RESTRICTIONS

Track-type equipment is not permitted on pavement that is not scheduled for removal unless the tracks are equipped with rubber or neoprene pads.

WORKING AREA

The Contractor may store equipment and stockpile material in the staging area designated by the Owner's Representative. Perform the Work so as to minimize damage. Restore all areas disturbed by the Contractor to the satisfaction of the Owner at the Contractor's expense.

CONSTRUCTION STAKING

The Owner will provide one-time layout of the court pavement limits, grading and construction limits and will provide requested construction staking once, on two working days' notice. Re-staking is at the Contractor's expense. The Contractor shall lay out fence lines from the dimensions on Sheet C101.

LABOR COMPLIANCE

Labor compliance requirements, including the applicable wage decision, classification statement and certified payroll, are stated in Section 00 0800, paragraph SC-3.4. The drawings do not establish whether prevailing wage requirements apply.

1. MOBILIZATION & TRAFFIC CONTROL, COMPLETE

This item includes mobilization and demobilization of the Contractor's forces and equipment, traffic control devices, and safety fencing around the work site. Provide barricades, signs and warning devices wherever pedestrians or trail users are affected, in accordance with the Manual on Uniform Traffic Control Devices. Keep the park entrance drive open throughout

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

the Work. Payment will be made in two parts: 50 percent in the first Application for Payment and 50 percent after Substantial Completion, both subject to retainage. Payment will be made at the lump sum price bid for MOBILIZATION & TRAFFIC CONTROL, COMPLETE.

2. EARTHWORK, COMPLETE

This item includes all earthwork and grading needed to reach finish subgrade and rough grades shown on the plans, including stripping topsoil, furnishing fill if required, hauling, placing and compacting on-site material, and removing excess or unsuitable material. Fill placed on the site under an earlier project has no compaction records. Strip topsoil, excavate the upper 2.5 feet of soil below the court subgrade elevation, and replace it in 8 inch lifts compacted to 95 percent standard Proctor density at plus or minus 3 percent of optimum moisture. Before placing aggregate base, proof-roll all paved areas with a loaded tandem axle dump truck of 20 tons minimum. Remedy areas that rut 1 inch or more by discing and drying, and proof-roll them again. Earthwork volumes, if provided, are for convenience only and do not adjust the lump sum price. Removal and replacement of unsuitable material is paid separately. Payment will be made at the lump sum price bid for EARTHWORK, COMPLETE.

3. TOPSOIL, FURNISH AND PLACE

This item includes furnishing, hauling and placing topsoil on exposed earth surfaces. Imported topsoil shall be uniform, free of hard clods, roots, sod, stiff clay, hardpan and stones over 1 inch, with at least 3 percent organic matter (ASTM D2974), a pH of 6.0 to 8.0 and no herbicide residue, and is subject to Owner approval. Place and spread to an uncompacted depth of 6 inches and finish to the plan grades. Payment will be made at the unit price bid per cubic yard for TOPSOIL, FURNISH AND PLACE.

4. AGGREGATE BASE, 8"

This item includes shaping and compacting the subbase and furnishing, placing and compacting an 8 inch granular base under all pavement to 95 percent standard Proctor density. The base extends one foot beyond the edge of pavement. Aggregate shall meet the state department of transportation standard specification for granular base, gradation 14. Recycled concrete is not allowed. Spread and compact with a steel drum roller. The Owner's Representative may proof-roll or test density. Payment will be made at the unit price bid per square yard for AGGREGATE BASE, 8".

5. ENGINEERED POLYMER GRID

This is a contingency item. It includes furnishing and placing a biaxial polymer grid to stabilize subgrade under the pavement where directed by the Owner's Representative because unsuitable material is found. The Owner may add or deduct quantity at the unit price bid. The Contractor is paid for the area actually covered, which may be zero. For bidding, assume the grid is needed under one half of the pavement. Pay limits are the area covered, regardless of overlap. Payment will be made at the unit price bid per square yard for ENGINEERED POLYMER GRID.

6. 3" HMA SURFACE

This item includes furnishing, placing and compacting hot mix asphalt in accordance with the state department of transportation standard specifications for hot mix asphalt, as modified here. The asphalt contractor shall have at least five successful tennis or pickleball court installations in the past 10 years and shall list them with references in the Bid. Submit the mix design for approval two weeks before placement. Mix: 300,000 ESAL, 3/8 inch nominal aggregate, PG 58-28 binder, placed in two 1-1/2 inch lifts. Apply tack coat between lifts at 0.02 to 0.05 gallon per square yard; tack coat is incidental. Use automatic screed control. The finished surface shall not vary more than 3/8 inch from design grade, shall not vary more than 1/4 inch in 10 feet in any direction, and shall have no deviation greater than 1/8 inch in 18 inches. Correct deficiencies at no cost to the Owner. Payment will be made at the unit price bid per square yard for 3" HMA SURFACE.

7. PCC SIDEWALK, 4"

This item includes furnishing and placing 4 inch Portland cement concrete walk on a prepared base, with joints, broom finish and curing, at the locations shown on Sheet C101 and connecting the courts to the existing path. Payment will be made at the unit price bid per square yard for PCC SIDEWALK, 4".

8. ACRYLIC COURT SURFACING

This item includes furnishing and applying an acrylic court surfacing system: patch binder mix for depressions, crack filler, acrylic filler course, color playing surface and line paint. All materials shall be from a single manufacturer, carry an ITF classification certificate, pass a 1,000 hour UV test and have an ITF pace rating of Category 2. The applicator shall hold the

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

manufacturer's authorized applicator certificate and shall list at least five similar projects from the past two years. Record the batch number of each product and keep the record through the warranty period of at least one year. Submit manufacturer data, color chart, applicator certificate, ITF certificate and reference list. Systems from multiple manufacturers are not accepted.

Allow new asphalt to cure 14 calendar days before application. Clean the surface by pressure washing and treat algae. Fill depressions that hold water the depth of a five cent coin with patch binder mix, struck off with a straightedge. Apply two coats of acrylic filler on new asphalt and two coats of the color playing surface, each allowed to dry. Lay out 2 inch wide lines to pickleball federation dimensions, taped for a crisp edge. Apply the surfacing over the entire paved court area within the fence and about 10 inches beyond. Do not apply it on the connecting paths. No work beyond patching shall begin until the Owner's Representative accepts the surface. Payment will be made at the unit price bid per square yard for ACRYLIC COURT SURFACING.

9. NET, COMPLETE

This item includes furnishing and installing a complete net assembly: two net posts with ground sleeves and footings, a center strap anchor with footing, and a net with center strap. The Contractor furnishes all materials, including footing concrete, labor and equipment. Payment will be made at the unit price bid per each of NET, COMPLETE.

10. 120" CHAINLINK FENCE (TYPE A)

This item includes all labor, materials and equipment required to install the 10'-0" high chain link perimeter fence in accordance with Sheets C101 and F501 and Section 32 31 13, including posts, core drilled footings, rails, braces, fabric and tension wire. The item does not include gates, windscreen or fence guard. Measurement is along the fence centerline excluding gate openings. Payment will be made at the contract unit price per linear foot of 120" CHAINLINK FENCE (TYPE A).

11. 42" CHAINLINK DIVIDER FENCE (TYPE B)

This item includes all labor, materials and equipment required to install the 42" high chain link court divider fence in accordance with Sheets C101 and F501 and Section 32 31 13, including posts, core drilled footings, top rail, fabric and tension wire. Payment will be made at the contract unit price per linear foot of 42" CHAINLINK DIVIDER FENCE (TYPE B).

12. GATE G1, 48" WIDE, 84" TALL

This item includes all labor, materials and equipment required to install the pedestrian swing gate shown on Sheet F502, including gate posts, core drilled footings, frame, fabric, header rail, fixed transom fabric, hinges, latch and hold-back. Payment will be made at the contract unit price per each of GATE G1, 48" WIDE, 84" TALL.

13. GATE G2, 72" WIDE, 84" TALL

This item includes all labor, materials and equipment required to install the maintenance swing gate shown on Sheet F502, complete as described for Gate G1. Payment will be made at the contract unit price per each of GATE G2, 72" WIDE, 84" TALL.

14. GATE G3, 84" TALL

This item includes all labor, materials and equipment required to install the service swing gate at the location shown on Sheet C101, complete as described for Gate G1. The clear opening width is as indicated on the Drawings. Payment will be made at the contract unit price per each of GATE G3, 84" TALL.

15. 9' WINDSCREEN, COMPLETE

This item includes all labor and equipment required to install a complete windscreen system on the inside face of the south Type A fence. The Contractor shall field measure the south fence after it is installed and shall order the windscreen from that measurement. The windscreen color is selected by the Owner from the manufacturer's standard colors. Payment will be made at the contract unit price per linear foot of 9' WINDSCREEN, COMPLETE.

16. FENCE GUARD

This item includes all labor, materials and equipment required to install fence guard on the top rail of the 42" high Type B divider fence, full length, in accordance with the manufacturer's recommendations. The fence guard is a UV-stabilized polyethylene cover of standard wall thickness in a color selected by the Owner from the manufacturer's standard colors.

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.

Payment will be made at the contract unit price per linear foot of FENCE GUARD.

17. BENCH, 6 FOOT

This item includes all labor, materials and equipment required to install a 6 foot long backless bench, with a powder-coated steel frame in a color selected by the Owner, mounted to the PCC sidewalk at locations designated by the Owner's Representative. Include all mounting hardware required by the manufacturer. Substitutions require a written submittal to the Architect at least 7 days before the bid date. Payment will be made at the contract unit price per each of BENCH, 6 FOOT.

18. SURFACE RESTORATION

This item includes furnishing and spreading topsoil, hydroseeding, fertilizing and hydromulching all disturbed areas. Place topsoil to a depth of at least 4 inches; stripped topsoil may be reused with approval if free of rock and debris. Seed shall be the state department of transportation permanent urban seed mixture at 4 pounds per 1,000 square feet. Fertilizer shall be 13-13-13 or equal at 750 pounds per acre. Hydromulch shall be an approved wood cellulose or bonded fiber matrix applied at the manufacturer's rate. Perform the work in the spring window (March 1 to May 31) or the fall window (August 10 to September 30). If seeding misses the window, scarify, apply temporary seed and straw mulch at no cost, and return in the next window. Water as needed to obtain 70 percent vegetative coverage within 21 days; remedy deficient areas at no cost. Payment will be made at the unit price bid per square yard for SURFACE RESTORATION.

19. TURF REINFORCEMENT MAT

This item includes furnishing and installing turf reinforcement mat on earth slopes, in accordance with the state department of transportation specification for Type 2 or 3 mat. After installation, place 1 inch of topsoil over the mat, then seed, fertilize and hydromulch. Payment will be made at the unit price bid per square yard for TURF REINFORCEMENT MAT.

20. ROLLED EROSION CONTROL PRODUCT, TYPE 2

This item includes furnishing and installing Type 2 rolled erosion control product on earth slopes, in accordance with the state department of transportation specification. Hydroseed the topsoil before installing the product. Payment will be made at the unit price bid per square yard for ROLLED EROSION CONTROL PRODUCT, TYPE 2.

21. EROSION CONTROL, COMPLETE

This item includes all labor, materials and equipment required to provide temporary erosion control for the duration of the Project. Provide a concrete washout if concrete trucks wash out on site. Install straw wattles, compost filter socks and silt fence downstream of all disturbed areas and around stockpiles. Payment will be made at the lump sum price bid for EROSION CONTROL, COMPLETE.

END OF SPECIAL CONDITIONS

FICTIONAL SYNTHETIC DEMONSTRATION - NOT FOR CONSTRUCTION. Issued for Bid (Synthetic). Prepared by IFI Labs / Synthetic CAD.